



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. - 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1970
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Orval Bridge of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Murfin Drlg. Co. guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company

Complete Address: 617 Union Center, Wichita, Kansas 67202

Lease Name: Sullivan "B" Well No. # 2

Location: NE SW SE Sec. 2 Twp. 14 Rge. 15 (E)(W) W

County: Russell Total Depth 3310 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Orval Bridge was instructed to plug the well as follows:

8 5/8" 154' Cwc.

No pipe recovery. Well previously squeezed. Run tubing to 2100',

circulated hole with mud to 340'. Pulled tubing, set plug @ 340',

& displaced 40 sack cement with Allied Cementing Company's pump truck,

cementing to base of cellar.

Very truly yours,

Don. Brown
Conservation Division Agent