



15-167-20051-0000

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027

3830 S. Meridian

WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION  
FEB 8 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Richard L. Mai of Richard L. Mai has this  
date requested permission to plug the following described well:

Mr. Richard L. Mai guarantees payment of the plugging fee.

Operator's full Name: Richard L. Mai

Complete Address: Box 606, Russell, Kansas 67665

Lease Name: Rouback Well No. # 12

Location: SW SW NW Sec. 2 Twp. 14 Rge. 15 (E)(W) W

County: Russell Total Depth 3284 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Delbert Adams was instructed to plug the well as follows:

8 5/8" csg. 914' Cwc. Set in Anhy.

Sanded hole back to 2900' & dumped 5 sax cement with dump bailer.

Pulled pipe. Mud to 375', set 25' rock bridge, & displaced 5 yds.

Ready-mix Cement, cementing from 350' to base of cellar.

Very truly yours,

  
Conservation Division Agent