

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY	Governor
WILLIAM L. MITCHELL	Chairman
JAMES O. GREENLEAF	Commissioner
HARRY G. WILES	Commissioner
RAYMOND B. HARVEY	Secretary
E. EDWARD JOHNSON	Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
OIL & GAS DEPARTMENT (STATE OF KANSAS)

NOV 27 1967

11-27-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed November 9, 1967.

Dear Sir:

Mr. Rod Sweetman of Sweetman Drilling Company has this date requested permission to plug the following described well:

Mr. Sweetman guarantees payment of the plugging fee.

Operator's full Name: Lee Phillips Oil Company

Complete Address: 1532 Wichita Plaza Bldg., Wichita, Kansas 67202

Lease Name: Mease Well No. # 1

Location: C SW NE Sec. 31 Twp. 30 Rge. 10 (E) (W) W

County Kingman Total Depth 4790' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Sweetman was instructed to plug the well as follows:

247' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill hole with drilling mud to 235', bridge with 1/2 sack of hulls the cement-plug, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent