

State of Kansas



15-145-20503-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS, 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 03 1978
CONSERVATION DIVISION
Wichita, Kansas
2-3-78

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Curtis of Duke Drlg. has this

date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.

Operator's full Name: WM. D. Witcraft

Complete Address: Box 811, Great Bend, Ks.

Lease Name: Compton Well No. 1

Location: SW NE SE Sec. 3 Twp. 22 Rge. (E)(W) 15

County: Pawnee Total Depth 3961' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Curtis was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 600' thru drill

pipe. Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey
Conservation Division Agent