

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bachus Oil Co.

Complete Address 721 E. Central Wichita, Ks

Lease Name Bertholf Well No. 1

Location SW/SW Sec. 1 Twp. 30 Rge. 10 (E) (W) W

County Kingman Total Depth 4675

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Clarke Oilfield Service Inc.

Address Chapin Bldg. Medicine Lodge, Ks License No. 583

Operation Completed: Hour 10:00 AM Day 9 Month 7 Year 1970

The above well was plugged as follows:

226 ft of 8 5/8 surface pipe circulated with cement. 4375 ft of 4 1/2
long string cemented with 100 sacks. Plug set at 2550 ft. Top perf.
2532. Sand back to 2522,ft, 3 sacks cement with bailer. Pulled 2270
ft of 4 1/2. Set 10 ft rock bridge at 200 ft. Redimix to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Y Russell Biberstein
Well Plugging Supervisor

DATE 7/13/70
INV. NO. 2206-W