

W
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 6 1964

1-6-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Bachus Oil Co.

Complete Address: 721 E. Central, Wichita, Kansas

Lease Name Demuth Well No. # 1

Location SW SW NE Sec. 1 Twp. 30 Rge. 10 (E) (W) W

County Kingman Total Depth 2600

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was washed down to a depth of 2600

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 11:00AM Day 3rd Month Jan. Year 1964

The Above well was plugged as follows:

321' of 8 5/8" surface pipe, cemented with 200 sacks. 2600' of 4 1/2" long
string, cemented with 125 sacks. Plug back to 2570'. Top perforation
2474'. Bottom of hole was sanded to 2460', and cemented with 3 sacks.
Fluid level was 275' in hole. Plug was set at 275', 10' rock bridge,
cemented with 25 sacks. Hole was filled with mud to 40', 10' rock bridge,
cemented with 10 sacks to base cellar.

1857' of 4 1/2" long string was recovered from the hole

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1/7/64

INV. NO. 8414-W