

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 130-3

LOCATION NW-NW-NW

SEC. 16 TWP. 22 RGE. 18

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Meckessel

Operator Great Bend Pipe & Supply Address Great Bend, Kans

Field _____ County Pawnee

Total Depth 4500 Feet.

Plugging Contractor West Supply Co. Inc.

Plugging Contractor's License No. 14

Address Chase, Kansas

(Describe briefly the manner in which the well was plugged)

*Surface pipe 8 7/8" @ 215' c.w.c. 5 1/2" Oil string
set 4375' w/ 175' sv cem. Top perf 4158'
sanded hole to 4145' dumped 5 sv cem.
Shot off and pulled 5 1/2" casing. Well
flowing. Pumped 20 sv fresh fill mud.
And 10 sv weight mud. Plug and 100 sv
cem. Filling hole and surface pipe from
approx 300' to base of cellar with cem.
Globe Cem. Co.*

RECEIVED Warren H. Horner
STATE CORPORATION COMMISSION District Conservation Agent

JUL 5 1955 Date June 30, 1955

CONSERVATION
Wichita

7-5-55

PLUGGING
FILE SEC 16 T 22 R 18 W
DESK PAGE 130 LINE 5