

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Icer Addis Oil Operations

Complete Address Box 519, Great Bend, Kansas 67530

Lease Name Meckfessel Well No. # 1

Location SE/4 NE/4 NE/4 Sec. 17 Twp. 22 Rge. 18 (E) (W) W

County Pawnee Total Depth 4204

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Knight Casing Pulling Company

Address Box 405, Chase, Kansas License No. # 436

Operation Completed: Hour 1 P.M. Day 19 Month 6 Year 1971

The above well was plugged as follows:

8 5/8" 1147' Cwc.

Sanded hole back to 4150' & dumped 5 sax cement with:dump bailer. Pulled pipe.

Mud to 425'. set 25' rock bridge, & displaced 6 yds. Ready-mix Cement, cementing

from 400' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/23/71
INV. NO. 3902-W

Signed: Don. [Signature]
Well Plugging Supervisor