

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name PERRY GAS COMPANY

Complete Address BOX 8929 - MIDLAND, TEXAS. 79703

Lease Name MECKFESSEL Well No. #1

Location N/2 - N/2 - SW Sec. 8 Twp. 22 Rge. 18 (E) (W) W

County PAWNEE Total Depth 2330 FE

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor PIPE PULLERS INC.

Address BOX 128 ELLENWOOD, KANS. License No. 462

Operation Completed: Hour 3:00 P.M. Day 19th Month JUNE Year 1979

The above well was plugged as follows:

8 3/8" 264 FE S.P. CMC 180 SX - 4 1/2" 2328 FE CMC 125 SX

PERIS. AT. 2200 FE -

PUT - 35 SX COMMON CMT. AT BOTTOM AND PUSHED PLUG.

to 1760 FE. - SHOT PIPE AT 1700 FE - NO PIPE RECOVERS.

ORDERED 110 SX COMMON CMT. 3% CR.-CL. (PUMPED IN WITH PUMP TRUCK)

PUT - 70 SX IN 4 1/2" CASING. - 50 LBS to 0'

40 SX IN THE ANNULUS - MAX PRESSURE 200 LBS to 50 LBS

CEMENTED BY SUN CEMENTING

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor
JUL 23 1979

INVOICED

DATE 7-24-79

INV. NO. 0071-W

7-23-79
CONSERVATION DIVISION
Wichita, Kansas