

1 120004

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- - 145-21,105-0000

C NW SE, SEC. 27, T 22 S, R 19 W

1980 FEET FROM W/S SECTION LINE

1980 FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5087

LEASE NAME Price WELL # 1-27

OPERATOR: Texas Energies, Inc.
NAME & P. O. Box 947
ADDRESS Pratt, KS 67124

COUNTY Pawnee

WELL TOTAL DEPTH 4450 144.63 FEET

CONDUCTOR PIPE: SIZE FEET

SURFACE CASING: SIZE 8 5/8 FEET 945 7.0

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Big Kat, Inc. LICENSE NUMBER 5839

ADDRESS Box 18154, Wichita, KS 67218

COMPANY TO PLUG AT: HOUR: 7:00 pm DAY: 17 MONTH: July YEAR: 19 84

PLUGGING PROPOSAL RECIEVED FROM Gary Pugh

(COMPANY NAME) Big Kat (PHONE) 316-458-4761

WERE: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1000' with 70 sx cement

2nd plug at 500' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

PLUGGING PROPOSAL RECEIVED BY David C. Uebel
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE X

OPERATIONS COMPLETED: HOUR: 8:30 pm DAY: 17 MONTH: July YEAR: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1000' with 70 sx cement, 2nd plug at 500' with 50
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement

7-19-84

RECEIVED
STATE CORPORATION COMMISSION

REMARKS: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

JUL 19 1984

CONSERVATION DIVISION
Wichita, Kansas

I ~~DOES~~ / DID NOT) OBSERVE THIS PLUGGING.

SIGNED David C. Uebel
(TECHNICIAN)

INVOICED

DATE 7-31-84

INV. NO. 2773

7-17

AUG 16 1984

FORM CP-2/3
REV. 6-83