

15-159-05537-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
Wichita, Kansas 67217

Rev. 3-15-72  
FORM CP-1

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 18 1973  
CONSERVATION DIVISION  
Wichita, Kansas

WELL PLUGGING APPLICATION FORM  
File One Copy

Lease Owner Thos. H. Allan  
Address 925 Union Center, Wichita, Kansas 67202  
Lease (Farm Name) Mayer Well No. #3  
Well Location NE SE SE Sec. 4 Twp. 22 Rge. 8 (E)      (W) X  
County Rice Total Depth 3421' Field Name       
Oil Well X Gas Well      Input Well      SWD Well      Rotary D & A       
Well Log filed with application as required Yes  
Date and hour plugging is desired to begin At Once

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

O. L. Goodwin Address Route #1 Great Bend, Kansas

Plugging Contractor Southwest Casing Pulling Co. License No. 399

Address Box 364 Great Bend, Kansas

Invoice covering assessment for plugging this well should be sent to:

Name Thos. H. Allan

Address 925 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: *S. O. Miller*  
Applicant or Acting Agent

Date: July 17, 1973

*Southwest Casing Pulling Co*

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3930 S. Meridian  
WICHITA, KANSAS 67217

July 18, 1973

WELL PLUGGING AUTHORITY

Well No.	3
Lease	Mayer
Description	NE SE SE 4-22-8W
County	Rice
Total Depth	3421'
Plugging Contractor	Southwest Casing Pulling Co.

Thos. H. Allan  
925 Union Center Bldg.  
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

*J. Lewis Brock*  
J. Lewis Brock, Administrator

Mr. Gilbert Toman Box 180 Holyrood, Kansas 67450  
is hereby assigned to supervise the plugging of the above named well.

## WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

15.159 05537 0000

508 East Murdock,

Wichita, Kansas


Company-ALLAN et al  
Farm- Mayer

No. 3

SEC. 4 T. 22 R. 8W  
NE SE SETotal Depth. 3421 RB. PB 3389  
Comm. 9-21-53 Comp. 10-13-53  
Shot or Treated.  
Contractor. Tom Allan  
Issued. 11-7-53

County Rice

KANSAS

Elevation. 1652 RB.  
EST.Production. 3,500,000 gas  
through 3/4" choke-  
shut in.

All Depths From Rotary Bushing Figures Indicate Bottom of Formations.

soil surface	20
sand, gravel	130
clay yellow	155
red beds	400
shale	700
salt, shale	1200
shale, anhydrite	1350
shale red	1360
lime, shale	2480
sand	2520
lime, shale	2885
sand, shale	2962
lime brown	2969
shale	2984
lime w/shale breaks	3095
lime soft oolitic	3109
lime with shale breaks	3220
lime soft oolitic	3225
lime	3289
shale, shells	3358
chert weathered & trip- oli- light stain	3371
chert wht & yellow Vitreous & wht weathered chert - light stain	3379
chert weathered - show of free oil in samples	3382
chert wht vitreous & weathered. Bailed 8 BOPH	3387
chert wht vitreous & weathered - No increase in oil	3417
lime buff crystalline	3418
shale red & green	3421
Total Depth RB	
PB 3389	
Tops: RB	
Brown Lime	2962
Lansing	2984
Mississippian	3358
Kinderhook	3418

## Testing:

DST 3338-69 - Open 20 mins.  
Gas to surface in 18 mins.  
Rec. 216' rotary mud. BHP  
shut in 15 min. 1135#.5 1/2" set at 3376' - clean out 3382  
No show.

3382-87- Bail 8 GOPH

3387-3421 - No increase

Plug back 3389 - Fracture with 80 bbl.  
heavy crude & 4000# sand.

Fractured into gas.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 18 1973  
CONSERVATION DIVISION  
Wichita, Kansas