

To: 1090644
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 083-21,421-0000
C NE NW, SEC. 16, T 22 S, R 24 W/E
4620 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30604

Lease Name Shriwise R Well # 1

Operator: Raydon Exploration, Inc.
Name & Address: 9400 N. Broadway, Ste. 400
Oklahoma City, OK 73114

County Hodgeman 156.00

Well Total Depth 4800 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 808

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address: P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 2 Month: 1 Year: 19 96

Plugging proposal received from David McIntyre

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 5 1/2" at 4800' w/100 sx cement, PBDT 4763', Perfs at 4668-72'

1st plug sand back to 4620' and dump 5 sx cement on top of sand through bailer.

2nd plug at 1700' with 50 sx cement and 17 sx gel.

3rd plug at 840' with 50 sx cement.

4th plug at 420' with 25 sx cement, 5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:30 p.m. Day: 2 Month: 1 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4620' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped 17 sx gel with 50 sx cement at 1700' through casing,

3rd plug pulled to 840' and pumped 50 sx cement.

4th plug pulled to 420' with 25 sx cement,

5th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3300' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION RECEIVED 1-5-96
JAN 5 1996

INVOICED
DATE: JAN 23 1996
Observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE: 44700
INV. NO. 44700