

To: 1 090791 3-23
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-083-21,439-0000
10' E of
W/2 W/2 NW, SEC. 16, T 22 S, R 24 W/2

TECHNICIAN'S PLUGGING REPORT

Operator License # 7567
Operator: Jack P. Bowles
Name & Address: P.O. Box 3285
Edmond, OK 73083-3285

1320 feet from NS section line
340 feet from WXX section line
Lease Name Shriwise Well # I
County Hodgeman 156.97
Well Total Depth 4830 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 326

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ O&A
Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co., Inc. License Number 5929
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 9 a.m. Day: 23 Month: 3 Year: 19 97
Plugging proposal received from Sally
(company name) Duke Drilling Co. (phone) 316-267-1331

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1739'
1st plug at 1740' with 50 sx cement, 2nd plug at 800' with 80 sx cement,
3rd plug at 350' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:45 a.m. Day: 23 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 1740' with 50 sx cement,
2nd plug at 800' with 80 sx cement,
3rd plug at 350' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

INVOICED
DATE 3-26-97
INV. NO. 47819
3-23

Signed _____
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 25 1997
CONSERVATION DIVISION
WICHITA, KANSAS

FOR KCC USE:

FORM C-1 7/91

EFFECTIVE DATE: 3-12-97
DISTRICT # 1
SCA7... Yes No

State of Kansas 15-083-21,439-0000
NOTICE OF INTENTION TO DRILL

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date March 12, 1997
month day year

Spot 10'E of
C-W/2 - W/2 - NW Sec 16 Twp 22S S, Rg 24W East West

OPERATOR: License # 7567
Name: JACK P. BOWLES
Address: P.O. Box 3285
City/State/Zip: Edmond, Oklahoma 73083-3285
Contact Person: Jack Bowles
Phone: 405/348-4074

1320 feet from ~~XXXXX~~ North line of Section
340 feet from ~~XXXXX~~ West line of Section
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Hodgeman

CONTRACTOR: License #: 5929
Name: DUKE DRILLING CO. INC.

Lease Name: SHRIWISE Well #: 1
Field Name: _____

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Lans, Miss

Nearest lease or unit boundary: 340'
Ground Surface Elevation: EST 2370' 2473' feet MSL

Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no

Well Drilled For: Well Class: Type Equipment:

X Oil ... Enh Rec X Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... GWWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes ... Other
... Other _____

Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 400' 780' PERMIAN

Surface Pipe by Alternate: X 2 200'
Length of Surface Pipe Planned to be set: 500' 200'

Length of Conductor pipe required: N/A
Projected Total Depth: 4755'

Formation at Total Depth: Mississippi
Water Source for Drilling Operations:
... well ... farm pond X other

If GWWO: old well information as follows:
Operator: _____
Well Name: _____
Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth: _____
Bottom Hole Location: _____

Will Cores Be Taken?: yes X no
If yes, proposed zone: _____

Exp. 9/7/97

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 25 1997

AFFIDAVIT

alt II 700' ~~AT~~ ~~REG.~~

RECEIVED
KANSAS CORPORATION COMMISSION

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-901, et. seq.
It is agreed that the following minimum requirements will be met:

CONSERVATION DIVISION
WICHITA, KS

Pusher Sally (Duke Drilling)
SPUD DATE 3-14-97 INIT. SW

LENGTH SURFACE PLANNED 200
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 5/8" @ 326 CONDUCTOR
ANHYDRITE T- B-1739 ELEVATION

TD 4830 FORMATION _____
RAN PIPE @ SX DV TOOL _____ ALT II DONE
_____ SX Y N

Arbuckle Plug @ _____ Ft. W/ _____ SX
Hug./Council @ _____ Ft. W/ _____ SX

Anhydrite Base @ 174' Ft. W/ 50 SX
1/2 Base Anyh. @ 800 Ft. W/ 80 SX

1/2, 1/2 Plug @ _____ Ft. W/ _____ SX
Bottom Surface @ 350 Ft. W/ 50 SX

40' Plug @ 410 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL _____ SX (Irr. Well _____ Pond _____)
TECHNICIAN SM DATE 3-20-97 Hauling _____

TYPE OF CEMENT 100/40 670 1/4 lb/sec
STARTING TIME 9:00 (AM/PM) DATE 3-23-97
COMPLETION TIME 10:45 (AM/PM) DATE 3-23-97

CEMENT COMPANY _____