

15-055-20042-0000 170P
D-17,093

1 030719

API NUMBER 15- 019, Completed 9-3-71

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW, SEC. 5, 'T 22 S, R. 33 W

TECHNICIAN'S PLUGGING REPORT

3300 feet from S section line

3300 feet from E section line

Operator License # 515.3

Lease Name Garden City B Well # 3 SWO

Operator: TEXACO, INC

County Finney 159.09

Name & Address 101 E. 11th

Well Total Depth 4895 feet

Liberat, KS. 67901

Conductor Pipe: Size _____ feet

Surface Casing: Size 9 5/8 feet 415

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor TEXACO, Inc License Number 5153

Address same

Company to plug at: Hour: 9:30 AM Day: 15 Month: 7 Year: 19 86

Plugging proposal received from B. D. HARRISON

(company name) TEXACO (phone) 316-275-6546

were: 5 1/2" set @ 4895 POTA @ 4392 Perfo @ 3833-4308-3934-4016

TUBING PAINTED @ 186' - Attempts to fish tubing inside outside casing between 128' - 165' Attempt to run 1" tubing reached 193'

1st plug: Pump 100sx class H cement down 5 1/2" followed by 300sx light cement w/ 1/4 # flow sent - 5 1/2" went on vacuum.

com't below Plugging Proposal Received by Dow Ubel (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:45 PM Day: 21 Month: 7 Year: 19 86

ACTUAL PLUGGING REPORT 2nd Pump annulus w/ 100sx - on vacuum.

3rd Pump 200 sx ligh down annulus - could circ 5 1/2" when pumping at a high rate - Shut in on vacuum - 4:30 PM 7-15-86 -

4th 7-21-86 - Pump 200sx down annulus - vac. - slight blow on 5 1/2"

5th Pump 140sx light 65/35 permit with 800 # hulls mix in followed by

Remarks: 600sx straight cement pumped up to 500 # & hold. 65/35 permit 10% 404 2% cc
(If additional description necessary, use BACK of this form.) Buy Well



INVOICED (and do not) observe this plugging.

Signed Steve Plunert (TECHNICIAN)

DATE JUL 23 1986

JUL 23 1986

INV. NO. 14502

7-23-86

AUG 29 1986 SEP 29 1986