

1 030657

API NUMBER 15-083-21,235-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NW SW, SEC. 16, T 22 S, R 21 W/E  
1980 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652  
Operator: Mustang Drilling & Exploration, Inc.  
Name & Address: P. O. Box 1609  
Great Bend, KS 67530

Lease Name Waterhouse Well # 1-16  
County Hodgeman 144.63  
Well Total Depth 4450 Mississippi feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1292

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mustang Drilling & Exploration, Inc. License Number 5652  
Address P. O. Box 1609, Great Bend, KS 67530

Company to plug at: Hour: 4:30 am Day: 5 Month: February Year: 19 86

Plugging proposal received from Mike Campbell

(company name) Mustang (phone) 316-792-7323  
Elevation 2157'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1289-1310'  
1st plug 30' below the base of the surface pipe with 40 sx cement

2nd plug at 390' with 30 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement.

Plug water well from bottom to top with cement

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 6:15 am Day: 5 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1322' with 50 sx cement, 2nd plug at 390' with 30 sx  
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with  
10 sx cement, 5th plug to circulate rat hole with 15 sx cement. Plugged water well with  
9 sx cement.

Remarks: Cemented by Allied.  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 11 1986

INV. NO. 12540  
2-5

RECEIVED  
STATE CORPORATION COMMISSION  
Steve Durrant  
(TECHNICIAN)

FEB 10 1986

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date January 21, 1986 month day year

API Number 15- 15-083-21235-0000 083-21,235 C... NW... SW... Sec... 16. Twp. 22... S. Rg. 21... 1980 Ft. from South Line of Section 4620 Ft. from East Line of Section (Note: Locate well on Section Plat on reverse side)

OPERATOR: License # 5652 Name Mustang Drilling & Exploration, Inc. Address P.O. 1609 City/State/Zip Great Bend, KS 67530 Contact Person James Meroney Phone 316-792-7323

CONTRACTOR: License # 5652 Name Mustang Drilling & Exploration, Inc. City/State Great Bend, KS 67530

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO X Expl X Wildcat Cable

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Nearest lease or unit boundary line 660 feet County Hodgeman Lease Name Waterhouse Well # 1-16 Ground surface elevation feet MSL Domestic well within 330 feet yes X no Municipal well within one mile yes X no Surface pipe by Alternate: 1 X 2 270 Depth to bottom of fresh water 300 Depth to bottom of usable water 300 Surface pipe planned to be set 1350 Projected Total Depth 4500 feet Formation Mississippi

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to RCC specifications. YES Cementing will be done immediately upon setting production casing. Date 1-3-86 Signature of Operator or Agent Exploration Manager

For RCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 300 feet per Alt. This Authorization Expires 7-6-86 Approved By 1-6-86

Spud - 1-28-86 - 8 5/8 + 350 + 1292'

PUSHER Mike Campbell TD 4450 FORMATION Mud SURFACE PIPE 8 5/8 @ 1292' ANHYDRITE 1289' ELEVATION 2157' 1310 STARTING TIME & DATE COMPLETION TIME & DATE 1st PLUG @ 30' B. B. SPT. W/ 40 SX 2nd PLUG @ 390 FT. W/ 30 SX 3rd PLUG @ 58 40 - FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ LUGS - SX

CEMENT COMPANY TECHNICIAN pectus plug 1st 13 22 w/ 40 2nd 390 w/ 30 3rd 40-0 SBR-10 4th 15 60/40 w/ 6 90 9 1/2" in water well called start 4:30 7:15

RECEIVED STATE CORPORATION COMMISSION FEB 10 1986 CONSERVATION DIVISION Wichita Kansas