

1 051750

11-29

API NUMBER 15- 145-20,610-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW SW, SEC. 3, T 22 S, R 20
330 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5817

Operator: Benson Mineral Group, Inc.
Name:
Address 1560 Broadway, Ste. 1900
Denver, CO 80202

Lease Name Smith Well / 1-3

County Pawnee

Well Total Depth 2481 80.63 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 294

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Benson Mineral Group License Number 5817

Address 1560 Broadway, Ste. 1900, Denver, CO 80202

Company to plug at: Hour: 2:30 p.m. Day: 29 Month: 11 Year: 19 93

Plugging proposal received from Murray Brooks

(company name) Benson Mineral Group (phone) 303-863-3500

Perfs: 4 1/2" at 2481' w/300 sx cement, PBTD 2479', Perfs at 2254-58, 2310-17'

1st plug pump down the 4 1/2" with 50 lbs. wood chips, 25 sx cement, 16 bbl. gel, 100 sx cement.

2nd plug pump down 8 5/8" X 4 1/2" annulus with 50 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 9:30 p.m. Day: 29 Month: 11 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped down the 4 1/2" with 50 lbs. wood chips, 25 sx cement, 16 bbl. gel, 100 sx cement. Maximum pressure 200 psi and shut in 100 psi.

2nd plug pumped down the 8 5/8" X 4 1/2" annulus with 50 sx cement.

Maximum pressure 500 psi and shut in 500 psi.

RECEIVED
STATE CORPORATION COMMISSION

DEC 06 1993

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Benson Mineral Group. No casing recovery.
(if additional description is necessary, use BACK of this form.)

1 (if not observed) observe this plugging.

Signed Richard W. Lacey
(TECHNICIAN)

INVOICE
Date 12-10-93
Inv. No. 39457