

1090449

8-5

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-20,995-0000
SW SW NE NE, SEC. 9, T. 7 S, R. 20 N/E
1155 feet from N section line
1155 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817
Operator: Benson Mineral Group, Inc.
Name & Address 1560 Broadway, Ste. 1900
Denver, CO 80202

Lease Name Jones Well # 2-9
County Pawnee
Well Total Depth 2420 78.65 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 7 feet 979

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Benson Mineral Group, Inc. License Number 5817
Address 1560 Broadway, Ste. 1900, Denver, CO 80202

Company to plug at: Hour: 10:45 a.m. Day: 3 Month: 8 Year: 19 94
Plugging proposal received from Phillip Kempton

(company name) Benson Mineral Group, Inc. (phone) 303-863-3500

Work: 4 1/2" at 2416' w/230 sx cement, PBD 2412', Perfs at 2252-56, 2306-12, 2379-84'
1st plug pump in 1 sx hulls and 25 sx cement over perfs,
2nd plug pump gel to 1000' and pump 60 sx cement to surface,
3rd plug hook onto backside and pump in 100 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 5 Month: 8 Year: 19 94

ACTUAL PLUGGING REPORT 8/3/94-pumped in 1 sx hulls and 25 sx cement over perfs,
8/3/94-pumped gel to 1000' and pumped 60 sx cement. Shut in pressure 400 psi.
8/5/94-Hooked onto backside and pumped in 100 sx cement. Maximum pressure 800 psi and shut in
500 psi.

RECEIVED 9-9-94
STATE CORPORATION COMMISSION
SEP 09 1994

Remarks: Used common cement with 4% gel by BMG. No casing recover
(If additional description is necessary, use BACK of this form.)

INVOICED XXXXXX observe this plugging.

DATE AUG 29 1994
INV. NO. 41058

Signed [Signature]
(TECHNICIAN)