

15-145-00462-0001

To: 1 050925
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Re-entered 8/4/61
NE NE NE, SEC. 9, T 22 S, R 20 (W/NE)
4950 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817

Lease Name Jones Well # 1

Operator: Benson Mineral Group, Inc.
Name & Address
1536 Cole Blvd., Suite 220
Golden, CO 80401

County Pawnee 151.61

Well Total Depth 4665' feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1425

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11 a.m. Day: 19 Month: 8 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 5 1/2" at 4665' PBTD 4368' Perfs at 4325-31, 4345-51, 4444-48'

1st plug sand back to 4275' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 19 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4275' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 900 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2215' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

8-25-87
RECEIVED
STATE CORPORATION COMMISSION
AUG 25 1987
CONSERVATION DIVISION
WICHITA, KANSAS

INVOICED

DATE 8-25-87

Signed Richard W. Lutz (TECHNICIAN)

INV. NO. 17950