

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-30008-00-00
Spot: CSWSESE Sec/Twnshp/Rge: 26-30S-9W
330 feet from S Section Line, 990 feet from E Section Line
Lease/Unit Name: HOLCOMB E Well Number: 1
County: KINGMAN Total Vertical Depth: 4380 feet

Operator License No.: 4706
Op Name: MESSENGER PETROLEUM, INC.
Address: 525 S. MAIN ST.
KINGMAN, KS 67068

Production Casing Size: 4.5 feet: 4377 150 SX CMT 8 1/4 35
Surface Casing Size: 8.625 feet: 219 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/02/2002 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JON F. MESSENGER Company: MESSENGER PETRO. CO. Phone: (620) 532-5400

Proposed Plugging Method: ACCORDING TO KCC DIRECTIONS.
RECEIVED
KCC DISTRICT #2
MAR 5 2003
3-5-2003
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 08/21/2002 1:00 PM KCC Agent: JACK LUTHI

Actual Plugging Report:
The Perfs were covered with sand to 4260' and capped with 4 sks of cement. Pulled stretch, casing parted at 1040'. Spotted 50 sks on top of fish. Pulled casing to 900', spotted 35 sks of cement. Pulled casing to 270', circulated cement to surface.

Remarks: ALLIED CEMENTING 60/40 POZ 4% GEL
Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

INVOICED
DATE 3-6-03
INV. NO. 2003061272