

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-00031-00-00  
Spot: CSWSWSE Sec/Twnshp/Rge: 29-30S-9W  
330 feet from S Section Line, 2310 feet from E Section Line  
Lease/Unit Name: GRAHAM Well Number: 1  
County: KINGMAN Total Vertical Depth: 4445 feet

Operator License No.: 31191  
Op Name: R & B OIL & GAS, INC.  
Address: 904 N. LOGAN PO BOX 195  
ATTICA, KS 67009

Conductor Pipe: Size feet: 8144.46  
Surface Casing: Size 8.625 feet: 4443 150 sx  
Production: Size 4.5 feet: 4443 100 sx  
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 02/20/2002 10:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RANDY NEWBERRY Company: R&B OIL AND GAS Phone: (620) 254-7251

Proposed Plugging Method: As KCC requires.

Plugging Proposal Received By: DOUG LOUIS WitnessType: Plugging Operations Were Not Witnessed  
Date/Time Plugging Completed: 02/22/2002 10:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4297' AND CAPPED WITH 4 SKS OF CEMENT. THE CASING WAS SHOT AT 2842' AND 1808'. RECOVERED CASING FROM 1808, AND PULLED TO 1350', SPOTTED 35 SKS OF CEMENT. PULLED CASING TO 900', SPOTTED 35 SKS OF CEMENT. PULLED CASING TO 250', AND CIRCULATED CEMENT TO SURFACE. PULLED REMAINING CASING AND TOPPED OFF CEMENT.


RECEIVED  
KCC DISTRICT #2  
SEP 16 2002  
WICHITA, KS

Remarks: ALLIED CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 9-17-02

INV. NO. 2003060509