

2-040553

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER: 15-095-01,315 - 0000

NE NE SE, SECTION 34 TOWNSHIP 30 RANGE 9W

OPERATOR LICENSE # 5003

2310 FEET FROM S SECTION LINE

330 FEET FROM E SECTION LINE

OPERATOR McCoy Petroleum Corp.

NAME & 110 South Main, #500

ADDRESS Wichita, KS 67202

LEASE NAME: Swingle #1

COUNTY: Kingman

WELL TOTAL DEPTH: 4440' 144.30

CONDUCTOR PIPE: " @ '

SURFACE CASING: 8-5/8" @ 236'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Hayes Well Service

ADDRESS: Attica, KS LICENSE: 5429

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Daryl Hanson

COMPANY NAME: McCoy Petroleum Corp. PHONE: _____

WERE: CIBP @ 4350' & 3 sx - 25 sx @ 1500' - 25 sx @ 1100' -
0 - 290' - 5-1/2" 4438' - top perf 4400'

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 16:30 DAY: 20 MONTH: 3 YEAR: 1990

ACTUAL PLUGGING REPORT:

A CIBP was set at 4350' & capped w/3-1/2 sx cmt -
5-1/2" csg rec from 3400' - pipe pulled to 1499' & 25
sx cmt spotted - 5-1/2" pulled to 1096' & 25 sx cmt
spotted - 5-1/2" pulled to 293' & cmt to surface

REMARKS: Howco 60/40 6% gel

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE: 9-6-90

INV. NO. 29214

Steve Van Gieson

Steve Van Gieson (AGENT)

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
REV. 3/90

RECEIVED
STATE CORPORATION COMMISSION
STATE OF KANSAS

AUG 31 1990

NK