

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-21041-00-02 <sup>01/02/8-20-01</sup>  
Spot: NWSENW Sec/Twnshp/Rge: 18-22S-17W  
1662 feet from N Section Line, 1410 feet from W Section Line  
Lease/Unit Name: STROBEL Well Number: 1  
County: PAWNEE Total Vertical Depth: 1175 feet

Operator License No.: 31930

Conductor Pipe: Size feet:

Operator Name: BLUERIDGE PETROLEUM CORPO

Surface Casing: Size 8.625 feet: 405

Address: PO BOX 385  
NESS CITY, KS 67560

Production: Size feet:

Liner: Size feet:

38.19

Well Type: DH

UIC Docket No:

Date/Time to Plug: 11/05/2000 9:00 PM

Plug Co. License No.: 31548

Plug Co. Name: DISCOVERY DRILLING

Proposal Rcvd. from: TOM ALM

Company: DISCOVERY DRILLING

Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 1120' WITH 40 SX CMT. 2ND PLUG AT 420' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER

Witness Type: Plugging Operations Were Not Witnessed

Date/Time Plugging Completed: 11/06/2000 1:15 AM

KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 1115' WITH 40 SX CMT. 2ND PLUG AT 540' WITH 80 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

11-28-00  
RECEIVED  
STATE CORPORATION COMMISSION

NOV 28 2000

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

CONSERVATION DIVISION  
Wichita, Kansas

Plugged through: DP

District: 01

Signed

Michael J. Maier

(TECHNICIAN)

INVOICED

DATE 11/28/00

INV. NO. 2001061024

NOV 17 2000

Form 6192/3

MP