

To: 1 031170
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-29
API NUMBER 15- 145-20,546-0000 386
SW SW SE, SEC. 11, T 22 S, R 17 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # _____
Operator: Kansas Corporation Commission
Name & Address _____

330 feet from S section line
2310 feet from E section line
Lease Name Fulton Well # 1
County Pawnee
Well Total Depth 4110 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 2 p.m. Day: 28 Month: 8 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service (phone) 316-672-2531

were: 5 1/2" at 4109' w/50 sx cement, PBD 1501', Perfs at 4028-34', Possible DV at 1000' - cement unknown
1st plug perforate 5 1/2" at 1067-1069' w/5 shots, pump 125 sx cement down 5 1/2" w/50 sx
squeeze at perfs.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5 p.m. Day: 29 Month: 8 Year: 19 91

ACTUAL PLUGGING REPORT Could not get to bottom.

1st plug perforated 5 1/2" at 1067-69' with 5 shots, pumped 125 sx cement down 5 1/2" with
50 sx squeeze at perfs.

RECEIVED
STATE CORPORATION COMMISSION

Annulus appears full of cement.

SEP 06 1991

CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Steve Durrant
(TECHNICIAN)