

1 040805 11-11

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D-17,210

NW NE NW, SEC. 24, T 22 S, R 18 W/EX
4950 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5086

Lease Name Blackwell Well # 2
County Pawnee

Operator: Pintail Petroleum Ltd.
Name & Address: 225 N. Market, Ste. 300
Wichita, KS 67202

Well Total Depth 4445 144.47 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 feet 272

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ X D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524-0347

Company to plug at: Hour: 2:30 p.m. Day: 11 Month: 11 Year: 19 93

Plugging proposal received from Mike Kelso
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 7" at 4395' with 150 sx cement, Open hole 4395-4445' 11-18-93

1st plug set CIBP at 2860' and dump 5 sx cement on top of CIBP.

RECEIVED
STATE CORPORATION COMMISSION

2nd plug perforate 7" at 1100', pump 180 sx cement,

NOV 18 1993

3rd plug pump down 7" X 10" annulus with 120 sx cement.

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:30 p.m. Day: 11 Month: 11 Year: 1993

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2860' and dumped 5 sx cement on top of CIBP,

2nd plug perforated 7" at 1100' and pumped down 7" casing with 180 sx cement.

Maximum pressure 225 psi and shut in 100 psi.

3rd plug pumped down 7" X 10" annulus with 120 sx cement. Maximum pressure 250 psi and shut in 0.

NOTE: Couldn't get below 2860' in 7". Either bad casing or junk in hole.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

INVOICED (if additional description is necessary, use BACK of this form.)
NOV 23 1993

I (did / did not) observe this plugging.
DATE _____

Signed *Steve Pfeifer* (TECHNICIAN)

INV. NO. 39289