

1030308

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-21,168-0000

C NE SW SW, SEC. 24, T 22 S, R 18 W/X
N SE Corner of
990 feet from ~~XXX~~ section line
4290 feet from W SE Corner of
W/X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name Sowers Well # 1

Operator: Vincent Oil Corporation

County Pawnee

Name & Address 125 North Market, Suite 1110

Well Total Depth 4375 142.19 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 465

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Wheatstate Oilfield Services, Inc. License Number 5149

Address P. O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 7:00 am Day: 25 Month: October Year: 19 84

Plugging proposal received from Dennis Petz

(company name) Wheatstate (phone) 316-672-7514

work: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1150' with 50 sx cement

2nd plug at 480' with 40 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Quirant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9:00 am Day: 25 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1150' with 50 sx cement, 2nd plug at 480' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate

mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

10-31-84

OCT 31 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Buie.

CONSERVATION DIVISION
Wichita, Kansas

(if additional description is necessary, use BACK of this form.)

(did not) observe this plugging.

Signed Steve Quirant
(TECHNICIAN)

INVOICED
DATE 11-7-84

INV. NO. 4696
10-25