

To: 1 120739
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-28 API NUMBER 15- 145-20,331-0001 16R
NW SW NW, SEC. 2, T. 22 S, R. 15 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767

Operator: Ritchie Exploration, Inc.
Name & Address: 125 N. Market, Ste. 1000
Wichita, KS 67202

3630 feet from S section line
4950 feet from E section line
Lease Name Blackwell Well # 1
County Pawnee 128.14
Well Total Depth 3943 feet

Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 624

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 28 Month: 9 Year: 19 92

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3941.5' w/125 sx cement, PBD 3888', Perfs at 3664-67', 3941-47'

1st plug sand 5 1/2" casing back to 3610' and dump 5 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx

gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 28 Month: 9 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3610' and dumped 5 sx cement on top of sand through bailer.

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement. 10-7-92

Maximum pressure 500 psi and shut in 300 psi.

RECEIVED STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2118' of 5 1/2" casing. OCT 7 1992

(If additional description is necessary, use BACK of this form.) CONSERVATION DIVISION WICHITA, KANSAS

INVOICED (could not observe this plugging.)

DATE 10-20-92

Signed Duane Rankin (TECHNICIAN)

INV. NO. 36510