

To: 1 060183
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-10 API NUMBER 15- 15-145-20271-0000 Drill Completion Date 11/7/72

NW SE NE, SEC. 3, T. 22 S, R. 15 W&E
3630 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name & Address 125 N. Market, Ste. 1000
Wichita, KS 67202

Lease Name Compton Well # 1
County Pawnee 127.98
Well Total Depth 3938 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 292

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 9:30 a.m. Day: 10 Month: 9 Year: 19 93

Plugging proposal received from Vernon Duntz
(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 5 1/2" at 3934' w/125 sx cement, Open hole at 3933-3938'
1st plug sand back to 3880' and dump 5 sx cement on top of sand through bailer,
2nd plug at 950' with 50 sx cement,
3rd plug circulate cement from 340' to surface.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 10 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3880' and dumped 5 sx cement on top of sand
through bailer,

2nd plug pumped 50 sx cement at 950',

3rd plug at 340' with 100 sx cement to circulate. Cement dropped.

4th plug filled with 30 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
SEP 14 1993

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 5 1/2" casing.
Wichita, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

DATE SEP 17 1993

Signed Glenn Barlow
(TECHNICIAN)

INV. NO. 38694