

To: 1 040789 9-27
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-20,296-0060
SE SE NE, SEC. 3, T 22 S, R 15 W/E
2970 feet from S section line
450 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name & Address: 125 N. Market, Ste. 1000
Wichita, KS 67202

Lease Name Compton Well # 2
County Pawnee
Well Total Depth 3935 127.88 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 940

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P.O. Box 347, Chase, KS

Company to plug at: Hour: 12 p.m. Day: 27 Month: 9 Year: 19 93
Plugging proposal received from Vernon Duntz, Jr.

(company name) Kelso Casing Pulling (phone) 316-938-2943
were: 5 1/2" at 3928.5' w/100 sx cement, Openhole 3928.5-3935'

1st plug sand back to 3860' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper
plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12:45 p.m. Day: 27 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug sanded back to 3860' and dumped 5 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Maximum pressure 1000 psi and shut in 650 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 5 1/2" casing.
If additional description is necessary, use BACK of this form.

I (did / observe this plugging.

INVOICED
DATE 10-8-93
INV. NO. 38903

RECEIVED
STATE CORPORATION COMMISSION
OCT 06 1993
Signed _____
CONSERVATION DIVISION
Wichita, Kansas
FORM CP-2/