

To: 1 030679
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-20,349-0000
NE NE SE, SEC. 3, T 22 S, R 15 W/E^X
2310 feet from S section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4767
Operator: Ritchie Exploration, Inc.
Name & Address: 125 N. Market, Suite 1000
Wichita, KS 67202

330 feet from E section line
Lease Name Stan Compton Well # 1
County Pawnee 128.28
Well Total Depth 3947 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 605

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:00 pm Day: 20 Month: March Year: 19 86

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3942' PBTD 3911.9' Open Hole from 3942-3947'

1st plug sand back to 3895' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:45 pm Day: 20 Month: March Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3895' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 900 psi and shut in 450 psi

Remarks: Recovered 2830' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

DATE APR 1 1986
INV NO 13239

Signed Steve Shumant (TECHNICIAN)
MAR 31 1986
3-31-86