

1 031091

8-21

316R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,127-0000

SE SW SE, SEC. 7, T 22 S, R 15 WXX  
330 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5114

Lease Name Armstrong Well # 1

Operator: National Development Company

County Pawnee 130.00

Name & Address 310 West Central, Suite 117

Well Total Depth 4000 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1026

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Lyons Well Service License Number 30375

Address

Company to plug at: Hour: 7:30 p.m. Day: 21 Month: 8 Year: 19 90

Plugging proposal received from

(company name) (phone)

were: 4 1/2" at 3998' w/150 sx cement, Perfs at 3890-94'

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:15 p.m. Day: 21 Month: 8 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped plug to 3750' with 25 sx common cement on top,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

released 8 5/8" wiper plug and pumped 150 sx cement.

Hooked to 8 5/8" to 500, shut in with 100 psi.

RECEIVED  
SEP 5 1990 9-5-90

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2066' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE: 9-14-90

Signed Steve Hunsicker (TECHNICIAN)

INV. NO. 29306

8-21 OCT 25 1990