

4-060866

D-17,656

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-20,809 0001

SE SW SW /4 SEC. 27, 16 S, 11 W
540 feet from S section line
4160 feet from E section line

Operator license# 6412Lease: Burmeister Well # B-3Operator: Sid TomlinsonCounty: Barton

Address: 424 NW 42nd St.
Oklahoma City, Ok 73118

Well total depth 3596 ^{116.87} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 365 feet

Aband. oil well____, Gas well____, Input well____, SWD X, D & A____Plugging contractor: Co Tools License# _____

Address: _____

Company to plug at: Hour: 1:00 P.M. Day: 11 Month: April Year: 1996Plugging proposal received from: Jim LineCompany: Consultant for Sid Tomlinson Phone: 405-521-1852

Were: Order 150 sxs 60/40 posmix - 8% gel and hulls.
30 sxs common with 2% gel and 3% c.c.

RECEIVED
KANSAS CORPORATION COMMISSION

RCWD
04-17-96 APR 17 1996

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[] CONSERVATION DIVISION
WICHITA, KS

Completed: Hour: 11:00 A.M., Day: 12, Month: April, Year: 1996

Actual plugging report: 8 5/8" to 365' w/250 sxs. 2 7/8" to 3581' with 100 sxs. Tied
onto tubing and pumped 25 sxs common, 3% c.c. and displaced to 1600'. Let set 1 1/2 hrs., but
was still not set. Mixed and pumped 50 sxs 60/40 posmix - 8% gel and 200# hulls and
displaced to 1000'+ at 750#. S.I.O.N. Pressured 2 7/8" to 400# and held. Perf at 740' and
pressured to 300#. Zone tight. Left pressure on and tied onto annulus. Mixed and pumped
60 sxs 60/40 posmix - 8% gel with Max. P.S.I. 300#. Tied onto 2 7/8" and broke down perfs.
Pumped 50 sxs 60/40 posmix - 8% gel and shut in with 600#.

Remarks: Halliburton Cementing.

Condition of casing(in hole): GOOD X BAD _____ Anhy.plugin: YES X NO _____
Bottom plug(in place): YES _____, CALC X, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING _____, CASING X. Elevation: 1936 GL

I did[X] / did not[] observe the plugging.DATE APR 22 1996INV. NO. 45378

4-12

DA. (agent)
Form CP-2/3