

8-10

6-050118

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-009-20,766

NW SE SW /4 SEC. 27, 16 S, 11 W
990 feet from S section line
3630 feet from E section line

Operator license# 6412

Lease Burmeister B well # 1

Operator: Sid Tomlinson

County Barton

Address: 1802 Wildwood Drive
Stillwater, Oklahoma, 74025

Well total depth 3425 feet
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 363 feet

111.31

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Haliburton License#

Address: Great Bend, Kansas

Company to plug at: Hour: PM Day: 10 Month: August Year: 1993

Plugging proposal received from: Sid Tomlinson

Company: Sid Tomlinson phone: 405-372-2833

Were: 8 5/8" surface casing set at 363' with 200 sx. 5 1/2" production casing set at 3424' with 250 sx. 8 5/8" and 5 1/2" annular space squeezed with 250 sx. PBSD 3404'. Anhydrite at 756'.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All [XX], Part [], None []

Completed: Hour: 6:20 pm, Day: 10, Month: August, Year: 1993

Actual plugging report: Perf at 770' and 1460' with 3 holes each. Down 5 1/2" pump 40 sx 60/40 poz, 10% gel, 200# hulls. Pump 8 sx gel. Pump 150 sx 60/40 poz, 10% gel, no pressure. Called for more cement. 100 sx 60/40 poz, 8% gel on location. Pumped 50 sx 60/40 poz, 8% gel, 550 max pressure, 500 shut in. Annular space pump 0 sx cement, 100# pressure.

STATE CORPORATION COMMISSION
RECEIVED
AUG 30 1993

CONSERVATION DIVISION
Wichita, Kansas
08-30-93
RCW

Remarks: Haliburton on location

Condition of casing(in hole): GOOD Z BAD Anhy. plug: YES X NO

Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO

Plugged through TUBING, CASING X Elevation: 1930 GL

I did [X] / did not [] observe the plugging.

Bruce D. Basye
Bruce D. Basye
(agent)

HO

INVOICED

DATE SEP 02 1993

INV. NO. 38529