

8-9

API NUMBER 15-009-15034-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW NE SW SEC. 27 T. 16 S. R. 11 W/E^{XX}

2710 feet from S section line

7630 feet from E section line

Lease Name Burmeister Well # 3

County Barton 109.52

Well Total Depth 3370 feet

Conductor Pipe Size feet

Surface Casing Size 10" feet 105

TECHNICIAN'S PLUGGING REPORT

Operator License # 5290

Operator: Hinkel Oil Co.

Name & Address 1016 Union Center Bld.

Wichita, Ks. 67202

Abandoned Oil Well xx Gas Well Input Well SVD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address Russell, Ks.

Company to plug at: Hour: PM Day: 8 Month: August Year: 19 90

Plugging proposal received from Lee Bieberlie

(company name) Hinkle Oil (phone)

were: Surface casing 10" set at 105 w/110 sks; 5 1/2" set at 3364 w/100 sks.

Sq at 379-540 w/11 sks 499 - 510 w/15sks. Run tubing to 3000;

sq w/60/40 poz 8% gel. Sq backside of 5 1/2 x 10" annular space. Holes in casing

from 257 to 2367.

Plugging Proposal Received by Marvin Miller
(TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part None

Operations Completed: Hour: 3:00PM Day: 9 Month: August Year: 19 90

ACTUAL PLUGGING REPORT Ran 2 1/2" tubing to 3017; pumped 150 sks 60/40 poz

8% gel w/200 lbs. hulls down tubing; circulated up 5 1/2". Pulled tubing to 913;

pumped 100 sks cement and 100 lbs. hulls cement circulated up 5 1/2". Pulled tubing;

put 150 sks cement down backside. Tied onto 5 1/2 casing and pumped 300 sks 60/40 poz

8% gel down. Displaced w/18 sks gel to 2200. August 9, 1990. Pumped 250 sks

65/35 poz 10% gel down 5 1/2". Max pressure 200 lbs. 50 lbs shut in. Pumped 30 sks

Remarks: on backside. 400 lbs. max.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE: 8-24-90

INV. NO. 29072

Signed Bruce Basye Marvin Miller
(TECHNICIAN) (TECHNICIAN)

AUG 17 1990