

2040197

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-095-21252-0000

C-NE1/4 SEC. 10, T. 30 S, R. 10 W/E

3960 feet from N1/4 section line

1320 feet from W1/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Katzer Well # A-1

Operator: Raymond Oil Co.

County Kingman 105.01

Name & Address One Main Place

Well Total Depth 3231 feet

Sut 900

Conductor Pipe: Size _____ feet

Wichita Ks. 67202

Surface Casing: Size 8 3/8 feet 250

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase KS

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Bob Brehaman

(company name) Kelso Casing- (phone) _____

were: 4 1/2 3230 Sanded off & bridged off

Perf 3156-60 @ 900' & 1200' ran tubing

2994-90 to Bottom spotted 35 sk of

TOC 2842 inside 4 1/2 cement - Top with 3 Hull, 15 gal

Bot. 6-26-85 1000 SW 283035 120 sk cement Rec 2216'

top 6-28-85 - 650 - 500 Plugging Proposal Received by Steve Jensen (TECHNICIAN)
Sun 283878

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1045 Day: 28 Month: 6 Year: 19 85

ACTUAL PLUGGING REPORT Kelso Casing moved in over hole and began dumping sand in hole to plug off perforations. The sand formed a bridge at 900', applied 1200# pressure to bridge in an attempt to push bridge down, No Luck. Called Sun Cementing and had them bring out there pump trucks.

Remarks: _____

(If additional description is necessary, use BACK of this form.)

INDEXED

DATE 7-10-85

INV. NO. 8828

STATE CORPORATION COMMISSION

0 Signed

CONSERVATION DIVISION
Wichita, Kansas

7-9-85
Steve Jensen
(TECHNICIAN)

RO

and pressured the well up to 1750# to push plug down, No luck. Called for tubing and Pulling Unit. Ran tubing to 900' and circulated sand bridge out into a pit. Went thru sand bridge at 950' & got a gas blow, ran 1 more joint of tubing and found nothing. Pulled tubing from well and released the Pulling unit.

Sun Cementing hooked back in to the casing and attempted to pump cement plug on bottom. No luck, well pressured to 1500# and held. Ran back in with a wire line and found another bridge at 1200'.

Called pulling unit back in and washed the bridge out with tubing. Found a piece of wood in the hole. Tubing was run to bottom and the hole was circulated clean.

Sun Cementing tied into the tubing and pumped and 35 sack plug of cement on bottom, (6-26-85 1600) ticket #203035.

Tubing was pulled from hole, the Pulling unit was released and the casing was killed.

The top was plugged by pumping the the 8⁵/₈ 3 sacks of hulls, 15 sacks of gel and 120 of cement. By Sun Cementing Ticket #283878 6-28-85 - mx 650. ST 500.