

1060131

TO: STATE CORPORATION COMMISSION 10-28

API NUMBER NA (15-083-10351)-0000
C NE NW SEC. 29, T 22 S, R 22 W

CONSERVATION DIVISION - PLUGGING SECTION 3300⁴⁶²⁰ FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3300 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME MILLER WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY HODGEMAN

OPERATOR LICENSE # 100 WELL TOTAL DEPTH 4520 FEET

OPERATOR: KCC FEE FUND #9900-24-001 PRODUCTION CSG: SIZE 5 1/2" @ 4511' WITH SX

NAME AND 130 S MARKET RM 2078 SURFACE CASING: SIZE 8 5/8" @ 288' WITH 225 SX

ADDRESS WICHITA, KS 67202

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR PLAINS, INC LICENSE NUMBER 4072

ADDRESS PO BOX 346, NESS CITY, KS 67560-0346

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 28 MONTH: 10 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MIKE MAIER

(COMPANY NAME) KCC (PHONE) 316-225-8888

WERE: OPEN HOLE

- 1) CHECK WIRELINE T.D. FOR PLUG BACK. IF POSSIBLE RUN TUBING TO 4500' AND SPOT 40 SX CEMENT MIXED WITH 200 COTTON SEED HULLS.
- 2) FREE POINT CASING AT ANHYDRITE (1450').
- 3) RUN TUBING TO 1450' SPOT 50 SX PLUG. 4) PULL TUBING TO 550', CIRCULATE CEMENT TO SURFACE WITH 200 SX.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 4:30 PM DAY: 28 MONTH: 10 YEAR: 1998

ACTUAL PLUGGING REPORT _____

1ST PLUG 40 SX CEMENT PUMPED TO BOTTOM. 2ND PLUG RAN LOG AND PERFORATED AT 570'. PUMPED 130 SX CEMENT WENT ON VACUUM. 3RD PLUG HOOKED ONTO BACKSIDE AND PUMPED 80 SX CEMENT. PRESSURED TO 600#. SHUT IN WITH 400#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Michael J. Maier
(TECHNICIAN) FORM CP-2/3

12-3-98

RECEIVED
 DIVISION OF
 STATE CORPORATION
 COMMISSION
 KANSAS
 OCT 31 1998