

15-009-03123-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER D&C 02-28-51 (of this well) 6/85  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Gulf Oil Corporation OPERATORS LICENSE NO. 5816

ADDRESS P.O. Box 12116, Oklahoma City, OK 73157 PHONE # (405) 949-7000

LEASE (FARM) Joseph WELL NO. 7 WELL LOCATION 1650 FWL COUNTY Barton  
2310 FSL

SEC. 29 TWP. 16S RGE. 11 (E) or (W) TOTAL DEPTH 3320' PLUG BACK TD Open Hole

Check One:

OIL WELL  GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 746' CEMENTED WITH 345 SACKS

PROD. CASING SIZE 5 1/2" SET AT 3317' CEMENTED WITH 100 SACKS

PERFORATED AT None - Open Hole 3317' to 3320'

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Shown on Back of Form.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No Record  
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN As Soon As Possible.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mr. C. T. Oglesby PHONE # (316) 265-3169

ADDRESS P.O. Box 2063, Wichita, KS 67201

PLUGGING CONTRACTOR Kelso Casing Pullers LICENSE NO. 6050

ADDRESS P.O. Box 347, Chase, KS 67524 PHONE # (316) 938-2457

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Dorretta Moore  
(Operator or Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 18 1985

DATE: April 15, 1985

NOTE: Mail P&A Approval To: CONSERVATION DIVISION 4-18-85  
Dorretta Moore  
c/o Gulf Oil Corporation, P.O. Box 12116, Okla. City, OK 73157

Mail P&A Invoice To: Gulf Oil Corporation, P.O. Box 2063, Wichita, KS 67201

6

Joseph #1, #3, #4, #5, #7, #8, #11, #12

Sec. 29-165-11W

Barton County, Kansas

Procedure to Plug and Abandon

- (1) MIRR P.U. MI  $2\frac{3}{8}$ " workstring.
  - (2) POH w/ rods + tbg.
  - (3) RIH w/ workstring to T.D. Circ. well full w/ 9" ppq, 36 vis. mud. (~ 85 bbls)
  - (4) Spot 50 sks of A cmt. (~ 400' cmt.)
  - (5) P.O.H. w/ tbg. W.O.C.
  - (6) Press test csg. to 100 psi.
  - (7) MI csg pullers. Determine free point of csg. Cut csg off.
  - (8) POH w/ csg to  $\pm 850'$
  - (9) Tie onto csg. Cut circ to surface.
  - (10) Circ. well full w/ 300 sks of A cmt w/ 4% gel. 7.8 gal wt. / sk cmt., 14.1 ppq, 1.55 cu ft cmt / sk.
  - (11) POH w/ csg. W.O.C.
  - (12) Top off well w/ cmt. Cut surface pipe off 6' below ground level. I.D. well. Restore surface.
- Note: If csg has holes in it, spot top plug with workstring.
- Note: Notify state man before plugging begins.

Noted \_\_\_\_\_

JMB

James Marshall  
3-14-85

Approved \_\_\_\_\_

CC: NET MFB, FSG, CTO(2), JEM,  
WELL FILE (orig)



WIN CARLIN  
MICHAEL LENNEN  
MARGALEE WRIGHT  
JITH R. HENLEY  
DITH A. McCONNELL  
IAN J. MOLINE

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary  
General Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
200 Colorado Derby Building  
202 West 1st Street  
WICHITA, KANSAS 67202-1286

### THIS NOTICE

JUL 18 1985

April 18, 1985

WELL PLUGGING NOTICE

EXPIRES

Joseph #7  
1650' FWL 2310' FSL  
Sec. 29-16S-11W  
Barton County

Gulf Oil Corp.  
P. O. Box 12116  
Oklahoma City, OK 73157

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to

DIST. #6 1014 Cody Hays, KS 67601 913-628-1200

five days prior to plugging the well (KAR-82-3-113).