

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-095-21,387-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR McCoy Petroleum Corporation KCC LICENSE # 5003
(owner/company name) (operator's)

ADDRESS 3017 N. Cypress CITY Wichita

STATE Kansas ZIP CODE 67226-4003 CONTACT PHONE # (316) 636-2737

LEASE Cornelius WELL# 1 SEC. 29 T. 30S R. 9W (East/West)

S/2 - NW - NE - SPOT LOCATION/QQQQ COUNTY Kingman

990 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1980 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET#

CONDUCTOR CASING SIZE SET AT CEMENTED WITH SACKS

SURFACE CASING SIZE 8-5/8" SET AT 255' CEMENTED WITH 225 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 4448' CEMENTED WITH 100 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Mississippian 4370-4385'

ELEVATION 1674 1684 T.D. 4450' PBTD 4406' ANHYDRITE DEPTH
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Sand back to 4320' & cap with 4 sx cement. Shoot & pull casing according to stretch. Pull casing to 1500' & spot 35 sx cement. Pull casing to 1050' & spot 35 sx cement. Pull casing to 310' & circulate cement to surface. Pull remaining casing & top off cement. 60/40 Poz, 4% Gel. Orders by Steve Van Gieson w/ KCC Wichita.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? IS ACO-1 FILED? Yes

If not explain why?

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Daryl Hanson PHONE# (316) 272-1296

ADDRESS Box 2250 City/State Garden City, KS

PLUGGING CONTRACTOR Shawnee Well Service KCC LICENSE #

ADDRESS P. O. Box 781624 PHONE # (316) 254-7893

PROPOSED DATE AND HOUR OF PLUGGING (If Known?)

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR/AGENT

DATE: 8-19-94 AUTHORIZED OPERATOR/AGENT:

(signature)

87846 RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1994
CONSERVATION DIVISION
WICHITA, KANSAS

21



Kansas Corporation Commission

Joan Finney, Governor Susan M. Seltman, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director Brian Moline, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

August 23, 1994

McCoy Petroleum Corporation
3017 N Cypress
Wichita KS 67226-4003

Cornelius #1
API 15-095-21,387
S/2 NW NE
Sec. 29-30S-09W
Kingman County

Dear Daryl J. Hanson,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #2
202 W. First, Suite 304
Wichita KS 67202
(316) 263-8809

William R. Bryson, Director Conservation Division
KCC, Conservation Division, Wichita State Office Building
130 S. Market, Room 2078, Wichita, Kansas 67202 (316) 337-6200