

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-095-01,315-0001 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR McCoy Petroleum Corporation OPERATOR'S LICENSE NO. 5003

ADDRESS 110 S. Main, Suite 500; Wichita, KS 67202 PHONE # (316) 265-9697

LEASE (FARM) Swingle "N" WELL NO. 1 WELL LOCATION SW SW NW COUNTY Kingman

SEC. 34 TWP. 30S RGE. 9W or TOTAL DEPTH 4440 PLUG BACK TD 4397

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8 SET AT 236 CEMENTED WITH 200 SACKS

CASING SIZE 5-1/2" SET AT 4438 CEMENTED WITH 100 SACKS

PERFORATED AT 4375-4381'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Set CIBP @ 4350'. Place 3-1/2 sx cement on top of plug.

Cut off casing @ approx. 3400'. Circulate hole. Set bottom of 1st plug @ 1500' w/25 sx.

Set bottom of 2nd Plug @ 1100' w/25 sx. Set bottom of top plug @ 295' to surface. Cement w/Pump truck using 60-40 (If additional space is needed use back of form.) Pozmix, 6% gel.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? Yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN _____ will notify _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: _____

Daryl Hanson PHONE # (316) 532-5292

ADDRESS Kingman, KS 67068

PLUGGING CONTRACTOR Hayes Well Service LICENSE NO. 5429

ADDRESS Attica, KS PHONE # (316) 254-7204

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: John Roy McCoy
(Operator or Agent)

DATE: 7-12-90

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1990
CONSERVATION DIVISION
Wichita, Kansas

7-16-90