

6 060141

API NUMBER 15-009-23344-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW, SEC. 28, T. 16 S, R. 11 W/E
2310 feet from N/S section line
1650 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5230

Lease Name Rous Well # B-1

Operator: Pet. Energy

County Barton

Name & Address 1st National Bank Building

Well Total Depth 3406 110.69 feet

Suite 415

Conductor Pipe: Size feet

105 N. Main Street

Surface Casing: Size 8 5/8 feet 332' w/195 sks.

Wichita, Ks. 67202

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, Kansas 67524

Company to plug at: Hour: 10:00 AM Day: 8 Month: February Year: 19 84

Plugging proposal received from Neal Peddicord

(company name) Kelso Casing Pulling (phone) (316) 938-2457

were: Ordered 165 sks 50/50 poz mix 40% gel 3% cal. cl., 15 sks. hulls and 8 5/8" plug.

RECEIVED

STATE CORPORATION COMMISSION

FEB 21 1984

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by *[Signature]*
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00 AM Day: 8 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 8 5/8" set at 332' with 195 sks. 9 1/2" set at 3406'

Top perf. at 3378' plugged bottom with 5 sks. cement, sand and 5 sks. cement
to 3330' Shot pipe 1 time and recovered 2526'. Pumped in 8 5/8" 4 sks. hulls, 25 sks
cement, 12 sks. gel, 40 sks. cement, 37 gel, 1 sk. hulls, released plug and followed
w/100 sks. cement w/500 pound pressure.

Remarks:

INVOICED

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 2-22-84

Signed *[Signature]*
(TECHNICIAN)

INV. NO. 0297