

4-010254

5-6 15-009-03100-000
D-13,660

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- - 1941

SW SE SE /4 SEC. 28 , 16 S, 11 W
330 feet from S section line
990 feet from E section line

Operator license# 6509

Lease: Esfeld Well # 6 SWD

Operator: Cla-Mar Oil Company

County: Barton 117.33

Address: P.O. Box 1197
Hays, Kansas 67601

Well total depth 3610 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 Inch @ 765 feet

Aband. oil well, Gas well, Input well, SWD X, D & A

Plugging contractor: Allied Cementing License#

Address: Russell, Kansas 67601

Company to plug at: Hour: 9:00 A.M. Day: 5 Month: May Year: 1997

Plugging proposal received from: Jim Clark

Company: Cla-Mar Oil Company Phone:

Were: Pump 75 sxs 60/40 pozmix - 10% gel down tubing to plug bottom. Let set overnight.
Perf tubing at approx. 2000' and circulate to surface.

Cemented in Tubing N. Deines 5-17-97

DUO 05-19-97

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 12:30 P.M., Day: 6, Month: May, Year: 1997

Actual plugging report: Pumpd 75 sxs 60/40 pozmix - 10% with 200# hulls. Let set overnight.
Perforated tubing at 1950'. Could not pump into, perf at 1500'. Circulated with 120 sxs
60/40 pozmix - 10% gel. Max. P.S.I. 1000#. S.I.P. 400#.

Remarks:

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING. Elevation: GL

I (and X) did not [] observe the plugging.

Carv M...
(agent)

(agent)

Form CP-2/3

INVOICED

DATE MAY 20 1997

INV. NO. 48139

110