

1060161

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-185-21,937-0000

NE NE NW, SEC. 30, T 22 S, R 12 W/XX

330 feet from N/S section line

2310 feet from W/X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8625

Operator: VAC Petroleum  
Name & Address: 6225 East Kellogg  
Wichita, KS 67218

CONSERVATION DIVISION  
Wichita, Kansas

FEB 15 1984

RECEIVED  
STATE CORPORATION COMMISSION

Lease Name Witt Well # 1

County Stafford

Well Total Depth 3800 123.50 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Cougar Drilling Co., Inc. License Number 5138

Address 555 North Woodlawn # 114, Wichita, KS 67208

Company to plug at: Hour: 5:00 pm Day: 13 Month: February Year: 19 84

Plugging proposal received from Gary Bagby

(company name) Cougar Drilling (phone) 316-659-3173

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 690' with 50 sx cement

2nd plug at 310' with 50 sx cement  
solid bridge

3rd plug hulls' - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement, 6th plug to circulate mousehole with 10 sx cement. Plug water well with 5 sx cement

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 8:15 pm Day: 13 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 690' with 50 sx cement, 2nd plug at 310' with 50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rathole with 15 sx cement, 6th plug to circulate mousehole with 10 sx cement. Plug water well with 5 sx cement.

Remarks: Use 60/40 Pozmix with 2% gel 3% cc. by Bouie  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-24-84

INV. NO. 0370

2-13

Signed Paul A. Luthi (TECHNICIAN) ✓