

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19339-00-00
Spot: SWSESE Sec/Twnshp/Rge: 20-30S-7E
339 feet from S Section Line, 1028 feet from E Section Line
Lease Name: STOLP Well #: 3
County: COWLEY Total Vertical Depth: 2884 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	2881		30 SX
SURF	8.625	26		19 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/16/2015 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: _____ Company: QUALITY WELL SERVICE, INC. Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/16/2015 12:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

PRIOR OPERATOR RON WHITEMAN DBA GEN DOR OIL CO. ATTEMPTED TO PLUG THE STOLP #3. OPERATOR TAGGED TD @ 2884 AND SANDED BACK TO 2820' & CAPPED WITH 7 SX CEMENT. OPERATOR SHOT SQUEEZE HOLES AT UNKNOWN DEPTH. 7-23-2013 OPERATOR PUMPED 140 SX 60/40 FOR TOP PLUG. UNKNOWN IF CEMENT CIRCUALTED. DANIELS READY MIX TICKET #028729.

7-16-2015 QWS RIGGED UP & CHECKED BACKSIDE. RAN 1" ON BACKSIDE AND TAGGED CEMENT 25' DOWN. TOPPED OFF BACKSIDE WITH 25 SX. RAN 1" INSIDE 5 1/2" AND TAGGED CEMENT AT 168'. PUMPED 55 SX TO SURFACE. TOPPED OFF WITH 5 SX.

Perfs:

Top	Bot	Thru	Comments
2881	2910		

Remarks: QWS TICEKT #6418. 60/40 4% GEL Control # 2015 0026 - 001

Plugged through: TBG

District: 02

Signed Jeff Klock DISTRICT SUPERVISOR
(TECHNICIAN)

KCC WICHITA
JAN 09 2017
RECEIVED