

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-19340-00-00
Spot: SESESE Sec/Twnshp/Rge: 20-30S-7E
324 feet from S Section Line, 311 feet from E Section Line
Lease Name: STOLP Well #: 4
County: COWLEY Total Vertical Depth: 3260 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2910		
PROD	5.5	3009		75 SX
SURF	8.625	45		40 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/17/2015 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: _____ Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/15/2015 12:00 AM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

7-17-2015, QWS RIGGED UP, DUG CELLAR & PIT, CUT SURFACE 4' BELOW GROUND LEVEL. PERFORATED AT 350'. STACKED OUT AT 630'. PULLED TO 620' AND PUMPED 105 SX CEMENT, CIRCUALTED INSIDE THE 5 1/2" CASING. HOOKED UP TO 5 1/2" CASING AND PUMPED 130 SX CEMENT. CEMENT CIRCUALTED AROUND TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2873	2885		MISSISSIPPI

Remarks: QWS TICKET #6419 60/40 4% GEL Control # 2015 0026 - 002

Plugged through: TBG

District: 02

Signed [Signature] DISTRICT SUPERVISOR
(TECHNICIAN)

KCC WICHITA

JAN 09 2017

RECEIVED