

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-20503-00-01
Spot: SWSWNESE Sec/Twnshp/Rge: 25-15S-9W
1613 feet from S Section Line, 1152 feet from E Section Line
Lease Name: DONALD KIHN Well #: 1
County: ELLSWORTH Total Vertical Depth: 3095 feet

Operator License No.: 5047 String Size Depth (ft) Pulled (ft) Comments
Op Name: RUPE OIL COMPANY, INC. PROD 4.5 3066 375 SX
Address: 111 WHITTIER # 1000 PO BOX 783010 SURF 8.625 240 150 SX
WICHITA, KS 67207

Well Type: SWD UIC Docket No: D19486.0 Date/Time to Plug: 12/28/2016 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: GLEN RUPE Company: RUPE OIL CO Phone: (316) 689-3520

Proposed Plugging Method: Plug and Abandon in accordance within rules and regulations of the State Corporation Commission.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 12/29/2016 10:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU , pull tubing. Perforate at 950', 650', and 290'. Run tubing to 2957' - stacked out, and pump 15 sx's common cement, circulating a lot of polymer out. Pull tubing to 2660' and pump 35 sx's common cement with 100#'s cotton hulls. Pull tubing to 950' and wait 1 hr. Tag cement at 2150'. Pumped 35 sx's common cement at 960' on 12-29-16 and pulled tubing to 290'. Waited 1 hr. and tagged cement at 570'. Circulated cement from 290' to surface. Pulled tubing out and topped off.

Perfs:

Top	Bot	Thru	Comments
3066	3195		
2660	2684		

INVOICED
JAN 09 2017

Remarks: FAILED MIT ON 10-14-16. WELL HAS HAD POLYMER ADDITIVES. GRESSELL PERF # 1475. COPELAND CEMENT # C-44421

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)