

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-097-21774-00-00  
Spot: SENWNEW Sec/Twnshp/Rge: 25-29S-16W  
4933 feet from S Section Line, 3592 feet from E Section Line  
Lease Name: PIESTER D Well #: 1  
County: KIOWA Total Vertical Depth: 5025 feet

Operator License No.: 31980  
Op Name: LOTUS OPERATING COMPANY, L.L.C.  
Address: 100 S MAIN ST, STE 420  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4610		WITH 2 SX CMT
CIBP		4714		
PROD	5.5	4812	2022	WITH 150 SX CMT
SURF	10.75	274		WITH 225 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/27/2016 9:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: ROBIN BROWN Company: LOTUS OPERATING Phone: (620) 546-4801

Proposed Plugging Method: CIBP @ 4610' WITH 2 SX CMT. PLUG AT 930' WITH 15 SX GEL & 50 SX CMT. PLUG AT 320' WITH 70 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/27/2016 10:50 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4610' WITH 2 SX CMT. 1ST PLUG AT 910' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 292' WITH 70 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT. CMT CIRCULATED & THE HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4798	4806		
4718	4730		
4660	4674		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

INVOICED  
JAN 09 2017

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
DEC 28 2016  
KCC DODGE CITY