

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-22056-00-00
Spot: SWSE Sec/Twnshp/Rge: 18-34S-33W
660 feet from S Section Line, 2006 feet from E Section Line
Lease Name: BROWN Well #: 2-18
County: SEWARD Total Vertical Depth: 6672 feet

Operator License No.: 5263
Op Name: MIDWESTERN EXPLORATION COMPA
Address: 3500 S BOULEVARD STE 2B
EDMOND, OK 73013

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6115		WITH 2 SX CMT
COND	20	40		8 SX GROUT
PROD	4.5	6380	1796	WITH 250 SX CMT
SURF	8.625	1600		WITH 580 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/27/2016 10:30 AM
Plug Co. License No.: 5112 Plug Co. Name: MIDWESTERN WELL SERVICE, INC.
Proposal Rcvd. from: MARTY BAUER Company: MIDWESTERN WELL SERVICE, IN Phone: (620) 624-8203

Proposed Plugging Method: CIBP @ 6115' WITH 2 SX CMT. PLUG AT 1640' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/27/2016 3:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 6115' WITH 2 SX CMT. 1ST PLUG AT 1645' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 610' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT. TOP OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6240	6250		
6230	6236		
6210	6230		
6188	6200		
6165	6178		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

INVOICED

JAN 09 2017

District: 01

Signed BWB

(TECHNICIAN)

RECEIVED
DEC 30 2016
KCC DODGE CITY

SA