

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-057-20647-00-02  
Spot: NWSENWNW Sec/Twp/ship/Rge: 21-27S-23W  
4574 feet from S Section Line, 4460 feet from E Section Line  
Lease Name: MAVERICK Well #: 1  
County: FORD Total Vertical Depth: 5105 feet

Operator License No.: 4767  
Op Name: RITCHIE EXPLORATION, INC.  
Address: 8100 E 22ND ST N # 700 BOX 783188  
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	80		WITH 9 SX CMT
PC		1336		WITH 225 SX CMT
PROD	4.5	5097	0	WITH 200 SX CMT
SURF	8.625	437		WITH 300 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/29/2016 10:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: GARY ROWE Company: RITCHIE EXPLORATION Phone: (620) 617-4671

Proposed Plugging Method: LOAD HOLE & ESTABLISH AN INJECTION RATE THROUGH PRODUCTION PERFORATIONS. PUMP 30 SX CMT WITH 200# HULLS, MUD SPACER & CMT TO SURFACE. PRESSURE BACKSIDE WITH CMT

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 12/29/2016 12:10 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

LOADED THE HOLE & ESTABLISHED AN INJECTION RATE OF 2 BPM AT 800#. PUMPED 30 SX CMT WITH 200# HULLS, 46 BBL MUD SPACER TO 1400' & 100 SX CMT. PRESSURED TO 1400# & HELD AT 400#. BACKSIDE WAS FULL.

Perfs:

Top	Bot	Thru	Comments
4939	4946		

INVOICED  
JAN 09 2017

Remarks: USED 60/40 POZMIX 4% GEL 3% CC BY CONSOLIDATED.

Plugged through: CSG

District: 01

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
JAN - 3 2017  
KCC DODGE CITY [Signature]