

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-21181-00-00
Spot: NWSENE Sec/Twnshp/Rge: 20-21S-7W
3652 feet from S Section Line, 1320 feet from E Section Line
Lease Name: PHINNEY A Well #: 1
County: RICE Total Vertical Depth: 3955 feet

Operator License No.: 3911

Op Name: RAMA OPERATING CO., INC.

Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3509		100 SX
SURF	8.625	208		200 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/28/2016 12:00 AM

Plug Co. License No.: 34069

Plug Co. Name: BASIC ENERGY SERVICES, LP

Proposal Rcvd. from: RAMA OPERATING CO.

Company: RAMA OPR CO

Phone: (620) 234-5191

Proposed
Plugging
Method:

According to the rules and regulation of the KCC

Plugging Proposal Received By: B. J. HOPE

Witness Type: PARTIAL

Date/Time Plugging Completed: 12/29/2016 12:00 AM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, ck bottom depth. Set CIBP at 3370' and cap with 2 sx's cement. Cut casing off at 1200' and pull to 1100' and pump 50 sx's common cement. Pull casing to 600' and wait 1 hr. Tag cement with swab bar at 750'. Pumped 35 sx's at 600', pulled casing to 260' and circulated cement to surface. Pulled casing out and topped off.

Top	Bot	Thru	Comments
3420	3492		

INVOICED

JAN 09 2017

Remarks: TA - NOV WELL. GEMINI CIBP TICKET #2795. BASIC SVC'S TICKET #14730

Plugged through: CSG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

✓