

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-20011-00-00
Spot: NWSENENE Sec/Twnshp/Rge: 1-23S-10E
4320 feet from S Section Line, 348 feet from E Section Line
Lease Name: HARRIS A Well #: 1
County: GREENWOOD Total Vertical Depth: 2175 feet

Operator License No.: 6101
Op Name: TEICHGRAEBER OIL, INC.
Address: 700 N MAIN ST
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2174		70 SX
SURF	7	40		25 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/21/2016 10:00 AM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Rcvd. from: RICK STOUT Company: _____ Phone: (620) 583-2173

Proposed
Plugging
Method:

Per KCC recommendations

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: PARTIAL
Date/Time Plugging Completed: 12/21/2016 1:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

ran tubing to 1870', pumped 15 sxs cement, pulled tubing to 900', pumped 15 sxs cement, pulled tubing to 200', pumped 70 sxs cement to surface, gel spacers between cement plugs, casing shot @ 900' & 200'.

RECEIVED
KCC DIST # 3
JAN 03 2017
CHANUTE, KS

MH

INVOICED
JAN 09 2017

Remarks:

Plugged through: TBG

District: 03

Signed Mik [Signature]
(TECHNICIAN)

KCC WICHITA

JAN 06 2017

RECEIVED

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. 3085
 Foreman Russell mcloy
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
12-21-16	1045	Harris A-1	1	23 S	10 E	G.W.	KS
Customer Teichgraber Oil			Unit #		Driver		Unit #
Mailing Address 700 N. Main			102		Rick		
City Eureka			110		A-B		
State KS			141		Zevi		
Zip Code 67045							
Safety Meeting Rm Rick A-B Zevi							

Job Type P.T.A Hole Depth _____ Slurry Vol. 25 Bbl Tubing 2 3/8
 Casing Depth BA @ 1875 Hole Size 7 7/8 Slurry Wt. 13.8 Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK 6.5 Other _____
 Displacement 0 Displacement PSI _____ Bump Plug to _____ BPM 3

Remarks: Safety Meeting SPOT 15 SKS @ 1870
15 SKS @ 900'
70 SKS From 200' to Surface
100 SKS TOTAL
Good cement Returns to Surface.
APP No# 15-073-20011-00-00 Thank you Russ + crew

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-105	1	Pump Charge	750.00	750.00
		Mileage N.C. 1st of 2 wells	N.C.	—
C-203	100	SKS 6040 P.2mix Cement	12.75	1275.00
C-206	340#	Gel = 490	.20	68.00
C-108A	4.32	Toni's Rik Truck 1/2 of mil	200.00	200.00
C-113	2.5	hr 80 Bbl Unc Truck	85.00	212.50
KCC WICHITA				
JAN 06 2017				
RECEIVED				
			Sub Total	2505.50
			Sales Tax	187.91
Authorization by <u>Rick Stout</u>			Title <u>Co-Rep</u>	Total <u>2693.41</u>

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.