

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-20493-00-00  
Spot: SWNWNW Sec/Twnshp/Rge: 7-23S-11E  
4290 feet from S Section Line, 4778 feet from E Section Line  
Lease Name: EDWARDS D Well #: 1  
County: GREENWOOD Total Vertical Depth: 2052 feet

Operator License No.: 6101  
Op Name: TEICHGRAEBER OIL, INC.  
Address: 700 N MAIN ST  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2082		100 SX
SURF	7	100		50 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/21/2016 1:00 PM  
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC  
Proposal Rcvd. from: RICK STOUT Company: \_\_\_\_\_ Phone: (620) 583-2173

Proposed Plugging Method: Spot 25 sacks over the perforations from 2034' to 2046' and cement from 200' to surface with top plug or as recommended by the KCC.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/21/2016 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 2005', pumped 15 sxs cement, pulled tubing to 900', pumped 15 sxs cement, pulled tubing to 200', pumped 70 sxs cement to surface, gel spacers between cement plugs, casing shot @ 900' & 200'.

Perfs:

RECEIVED  
KCC DIST # 3  
JAN 03 2017  
CHANUTE, KS

mt

INVOICED  
JAN 09 2017

Remarks: &

Plugged through: TBG

District: 03

Signed Mike Heffern  
(TECHNICIAN)

KCC WICHITA

JAN 06 2017

RECEIVED

810 E 7TH  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**  
 Ticket No. 3086  
 Foreman Russell McLoy  
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
12-21-16	1045	EDWARDS D-1	7	23 S	11 E	G.W.	KS
Customer Teichgraber Oil			Unit #		Driver		Unit #
Mailing Address 700 N. MAIN			102		Rick		
City Eureka			110		A-B		
State KS			141		Zevi		
Zip Code 67045							

Job Type P.T.A. Hole Depth \_\_\_\_\_ Slurry Vol. 25 Bbl Tubing 2 3/8  
 Casing Depth B.P. 2010 Hole Size 7 7/8 Slurry Wt. 13.8 Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2 Cement Left in Casing \_\_\_\_\_ Water Gal/SK 6.5 Other \_\_\_\_\_  
 Displacement 0 Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM 3

Remarks: safety meeting SPOT 15 SKs @ 2005'  
 15 SKs @ 900'  
 70 SKs @ 200 to Surface.  
 100 SKs Total

API NO# 15-073-20493-00-00 GOOD cement RETURNS

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-105	1	Pump Charge 2 <sup>ND</sup> of 2 wells	500.00	500.00
		Mileage N.C.	-	
C-203	100	SKs 60/40 Pozmix cement	12.75	1275.00
C-206	340 #	Gel = 4%	.20	68.00
C-108	4.32	Tons tow mileage Bulk Truck 200 mi	200.00	200.00
C-113	2.5	hr 80 Bbl UAC Truck	85.00	212.50
THANK YOU! Russ + crew				
KCC WICHITA				
JAN 08 2017				
RECEIVED				
			Sub Total	2,255.50
			Sales Tax	169.16
Authorization by <u>Rick Stott</u>			Title <u>col REP</u>	Total <u>2424.66</u>

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.